

**HASIL EVALUASI SPSPL RENCANA ANGGARAN BIAYA
PEMBUATAN SARANA DINDING / WALL PANJAT TEBING**

NO.	URAIAN	Vol		Harga	
		SAT.	VOLUME	Harga. SAT. (Rp.)	JML. HARGA (Rp.)
I	PEKERJAAN WALL KATEGORI SPEED 3 x 15 m				
1	Block Panel fiberglass	m2	45,00	-	-
2	PEKERJAAN PONDASI				
3	GALIAN TANAH	m3	1,40	-	-
4	BEGESTING	m3	7,20	-	-
5	PEMBESIAN(Dengan Besi Ulir)				
	Foot Plate (Ø13)	Kg	314,541	-	-
	Pedestal; (Utama Ø13)	Kg	227,237	-	-
	Pedestal; (ring Ø8)	Kg	70,54	-	-
	Sloof; (Utama Ø10)	Kg	131,129	-	-
	Sloof; (ring Ø8)	Kg	63,84	-	-
6	BETON MUTU f'c = 19,3 Mpa (K250)				
	Foot Plate & Pedestal	m3	5,40	-	-
	SLOOP	m3	1,50	-	-
7	PEKERJAAN BAJA				
	Baja Profil L 80.80.8 (Tiang Utama)	Kg	521,60	-	-
	Baja Profil L60.60.6 (Horizontal)	Kg	731,70	-	-
	Baja Profil L50.50.5 (Diagonal)	Kg	787,50	-	-
	Baja Profil L 5x5.4 (Belalai)	Kg	38,00	-	-
	Kawat las	pack	5,00	-	-
	Mata gerinda potong	Pack	5,00	-	-
	Mata gerinda penghalus	Pack	1,00	-	-
	Plat Pengaku/Conector	Kg	348,00	-	-
	Plat Conector Panel	Kg	74,00	-	-
	Baut Mur	Pcs	2796,00	-	-
	Besi Plat Tapak (Foot Plate)	Kg	84,90	-	-
	Baut Angkur Ø22 mm x 60cm	Pcs	16,00	-	-
				JUMLAH II	-
				JUMLAH HPS	-
				PPN 11 %	-
				JUMLAH + PPN	-
				PEMBULATAN	-
Terbilang Dua Ratus Juta Empat Ratus Tiga Puluh Tiga Ribu Rupiah					